

STATEMENT OF WORK

CSMS #1 VEHICLE WASH RACK AT BUILDING 117B, KALAELOA,
STATE OF HAWAII, DEPARTMENT OF DEFENSE,
HAWAII ARMY NATIONAL GUARD, JOB NO. CA-1424-C
MAY 20, 2016

The project consists of, but not limited to, providing a closed loop "Zero Discharge" stationary wash rack system completed with a roof, filtration system with integrated drag conveyor, 2,600 gallon total system capacity, in ground concrete slab, troughs with automated conveyor for solids removal; trough system shall not have side troughs or shovel troughs, dual media filter configuration for suspended solids removal, heavy duty water cannon with industrial grade stainless steel pump, be able to recycle reclaimed wash water, filter out oils without the use of an oil water separator system and inject ozone to kill bacteria.

Additional Bid Item #1: Furnish and install Solar PV Panels and Structural support system to include all associated materials (inverters, wiring, tubing, LED fixture, etc.) required to provide a functional working system.

In addition, include; structure number (2 each) signs, numbers shall be provided by the HIARNG, electrical infrastructure (trenching, conduits, hand hole etc.) connection for Building 117A (CIF), IT infrastructure (trenching, conduits etc.) from existing hand hole HH-2 to existing hand hole at Building 117A and electrical grid tie in to PV panels on wash rack roof.

The contractor shall examine the site of the proposed work and dully acquaint himself with the existing conditions relating to the construction and labor and should fully inform himself as to the site involved, the difficulties and restrictions attending the performance of the contract. The contractor thoroughly examine and familiarize himself with all contract documents. The contractor, by execution of the contract, shall in no way be relieved of any obligation due to his failure to receive or examine any form or legal instrument or to visit the site and acquaint himself with the existing conditions there and the Hawaii Army National Guard (HIARNG) will be justified in rejecting any claim as a result thereof.

The contractor shall be responsible for all damages and repairs to the existing site, to include, but not limited to, existing structures, under / above ground utility lines / pipes, landscape, paving, etc. Upon completion of operations, all existing items shall be in a condition equal to or better than that which existed before the construction.

All structures / work areas located in the general location of the site shall remain accessible and operational throughout the construction period. The contractor shall notify the HIARNG prior to any scheduled interruption.

The contractor shall be responsible, at his expense, to remove all construction debris, junk and trash from the site, leave the site in a clean condition (daily) and clean up all spillage and wind-blown debris from public and private lands.