

STATE OF HAWAII
DEPARTMENT OF DEFENSE
OFFICE OF THE ADJUTANT GENERAL
3949 DIAMOND HEAD ROAD
HONOLULU, HAWAII 96816-4495

May 31, 2018

ADDENDUM NO. 1

Regional Training Institute (RTI) Buildings Roof, Gutter, Downspouts Repair, Painting & Waterproofing, Waimanalo, State of Hawaii, Department of Defense, Hawaii Army National Guard, Job No. CA-1809

The items listed hereinafter are hereby made a part of the contract for the above mentioned project and shall govern the work taking precedence over previously issued contract documents governing the items mentioned. Receipt of this addendum is to be acknowledged on page OF-7 of the proposer's packet.

The following are questions submitted prior to the due date of May 25, 2018.

"During our site walk thru, we noticed that the existing PV panel to all buildings were installed with enough clearance from the metal roof to the bottom of PV panel mounting frame.

Also, there are existing wirings that are dropping and touching the metal roof."

1. Are we going to include in our bid to apply fluid applied roofing system underneath the existing PV panels?

A. Include in your bid the cost of cleaning the roof surface and application of fluid-applied bonding primer and water proofing system on all areas underneath the existing PV panels. This Addendum No. 1 shall supersede Item C.12.b (Notes / Important Instruction) of the Scope of Work/Specifications.

2. Are we going to include in our bid the existing wiring to secure properly to the PV panel mounting frame?

A. Do not include in your bid the cost of securing properly the loose wires underneath the existing PV panels. HIARNG/FMO Branch will contract out to an independent electrical Contractor, the work to fasten securely the loose wires and connectors to the PV panel frames.

3. When reviewing documents for this project, there were no specification sections. Please advise if there will be any specifications provided for each section.

A. Please read the Scope of Work/Specifications (SOW/Specs). If you are inquiring about the materials to be used and its generic specifications, you can find the answers under "Material Specifications"

4. The title of project says "Regional Training Institute Buildings Roof, Gutter, Downspouts Repair, Painting & Waterproofing", what areas will need to be painted? Plans are not clear of all areas. Please advise.

A. Again, please read the SOW/Specs. Work Items E.1 to E.4 specifically mention the areas to be painted (exterior surfaces of gutters, fascia, and downspouts).

5. Please advise as type of painting system will be required for areas needing painting.
 - A. If you are inquiring about the method of paint applications, it will be the Contractor's choice to use the method of application (brush, roller, or spray applied) provided that the Contractor protects the adjacent/nearby surfaces from paint splatters, smudges, and overspray. If you are inquiring about the rate or number of coats of application, please refer to work Item E.1 to E.4 of the SOW/Specs.*

Arthur J. Logan
Major General
Adjutant General

Posted: May 31, 2018